

International Atomic Energy Agency


Decommissioning Planning

Ingemar Lund - Swedish Radiation Protection Authority, SSI, Sweden

IAEA Regional Workshop: Legal and Regulatory Aspects of Decommissioning of Research Reactors Manila, Philippines, 26 -30 June 2006

























<section-header><section-header><section-header><section-header><list-item><list-item><list-item><list-item>






















Initial/ongoing and final planning during design, construction and operation	Sections 4 & 5	
•		IAEA Safety Guide WS-G-2.2
Decision to decommission		DECOMMISSIONING OF
Initial preparations (e.g. organization/administration quality assurance and training)		MEDICAL, INDUSTRIAL AND
(feedback)		RESEARCH FACILITIES
Facility characterization	Section 6 (6.1-6.6)	
(feedback)		
Select decommissioning option and end state objective	Section 3 (3.1)	
Prepare decommissioning plan	Section 5 Annex I	
↓		
Regulatory approval	Section 5 (5.7)	
Decommissioning implementation (see Fig. 2)		
Final radiation survey	Section 6 (6.17)	
Prepare final reports	Section 8 (8.1)	
↓		
Completion of decommissioning	Section 8 (8.3)	
FIG. 1. Flow chart for a typical decommi	ssioning project.	International Atomic Energy Agency







		TFTR Decommissioning Project PPPL Site, NJ		
Engineering (1.0)	Field Operations (2.0)	Project Management (3.0)	Health Physics & Safety (4.0)	Radioactive Waste Operations (5.0)
Oversight & Planning (1.1)	Oversight & Support (2.1)	Project Office (3.1)	Health Physics Oversight (4.1)	Radwaste Management (5.1)
Area Preparations (1.2)	Area Preparations (2.2)	Work Control Center (3.2)	Safety Oversight (4.2)	Containers and Supplies (5.2)
Non-Tokamak Removals (1.3)	Non-Tokamak Removals (2.3)	Configuration and Document Control (3.3)		Transportation and Disposal (5.:
Tokamak Removal Engineering (1.4)	Tokamak Removals (2.4)			Mixed Waste Management (5.4



Cost Elements				
Standardised List of Cost Elements (NEA / EC / IAEA)				
 01 Pre-decommissioning actions 02 Facility shutdown activities 03 Procurement of general equipment and material 04 Dismantling activities 05 Waste processing, storage and disposal 06 Site security, surveillance and maintenance 07 Site restoration, cleanup and landscaping 08 Project management, engineering and site support 09 Research and development 10 Fuel and nuclear material 11 Other costs 				
alsoLabour, Capital Equipment and Material, Expenses, and Contingency.				
http://www.nea.fr/html/rwm/reports/1999/costlist.pdf				
International Atomic Energy Agency				

