Report of Working Group 3

On "Materials Management Including Building Release and Clean-Up of the Site"



"HORIA HULUBEI" NATIONAL IN STITUTE FOR PHYSIC'S AND NUCLEAR ENGINEERING IFIN-HH Bucharest

407 Jamisha Sport Misseak ind Rics, P.O.B. MG-4, 077:125 ROMANIA, 077:125 P.O.MANIA, 0,000, pissea, p. 04021) 404-23.01, fix. +(4021) 457-44.40, 0000, pissea, p.

DECOMMISSIONING PLAN OF VVR-S RESEARCH NUCLEAR REACTOR

REVISION No. 9



BUCHAREST, MAGURELE



10th Workshop on the Review of a
Romanian Decommissioning Plan
in Conjunction with
Research Reactor Decommissioning and
Demonstration Project (R2D2P)
4 – 8 July 2011
Bucharest-Magurele, Romania

Group Members

- 1. Pablo Grossi Brazil;
- 2. Endang Kurnia Indonesia;
- 3. Anwar A. Fattah Ahmed Iraq;
- 4. Ibrahim Muhamad Malaysia
- 5. Antonio Hernandez Maldonado Mexico;
- 6. John M. Marquez Philippines;
- 7. Radojica Pesic Serbia; and
- 8. Romanian collegues;

Expert Consultant: Mr. Patrick O'Sullivan



...after initial Brainstorm


- Basic Concept of Material Management;
- Material Management;
 - Waste Management Plan
 - Classification of Waste
 - Radwaste
 - ➢ Non-Radwaste
 - > Treatment and Conditioning
 - > Transport
 - ➤ Storage and Disposal
 - Decontamination Plan
 - Control and Surveillance
- Clean-up and Release of Building and Site;
- Final Radiation Survey



SAFETY REPORTS SERIES No. 45

STANDARD FORMAT AND CONTENT FOR SAFETY RELATED DECOMMISSIONING DOCUMENTS

- 3. DECOMMISSIONING PLAN DETAILS
- 3.7. Waste Management
- 3.15. Final Radiation Survey
- 4. RELATED DOCUMENTS
- 4.3. Final Radiological Survey Plan





Results of the Evaluation

An evaluation of the DP for the topics of WG#3 was performed as follows:





Conclusions and Recommendations (1/5)

- Considering the results of the assessment, the activities listed on phase 1 of the DP are authorized.
- ➤ Before starting decontamination and dismantling the following documents should be provided for approval:
 - > Waste Management Plan
 - > Decontamination Plan
 - Final Radiation Survey Plan (before phase 3)



Conclusions and Recommendations (2/5)

- The description of the procedures for:
 - Waste Tracking System
 - Treatment; Conditioning; Packaging; and Storing of waste on-site (prior to shipment for disposal) for solid, liquid and mixed.
 - Measures to reduce the volume of waste
 - Monitoring; Assaying; and characterizing the waste for solid, liquid and mixed.



Conclusions and Recommendations (3/5)

- The following requirements should be complied:
 - Limit levels for each different waste classification should be provided, to allowing a reliable estimation of the volume of different waste classes. How the assessment of waste generated (Appendix 7.2.1) was performed without this limits?
 - Need to consider soil as one of identified solid waste to be managed.
 - The disposal of the resins should be defined.



Conclusions and Recommendations (4/5)

- The following requirements should be complied:
 - The radionuclide inventory and when it will be generated should be mentioned for solid, liquid and "mixed" radioactive waste.
 - A summary of the types of solid and liquid waste containing both radioactive and other hazardous materials expected to be generated during the decommissioning process.



Conclusions and Recommendations (5/5)

- The WG#3 consider that independent authorizations for each decommissioning phase could eventually drive to a non-completion of whole decom. process:
 - Some documents cited on DP are not available because they were not prepared yet, just general directives were given
 - Some regulatory requirements could never be achieved after starting decommissioning activities (it is a probability!!!)
 - ➤ It is necessary to have well established limits for each authorized phase (divergences between Reg. and Oper.)
 - Positive point: gradual approach to the decommissioning planning and activities



End Slide

Mulţumesc !!!

Thank you for your attention!

