



Australian Government

Australian Nuclear Science and Technology Organisation

HIFAR QMS, Characterisation & Transition Scheduling

Presenter: Algis Lencus



Outline

- Scheduling for Transition
- Radiological Characterisation
- HIFAR Quality Management System



HIFAR *transition* to Green Field





Scheduling for Transition

- Phase A – Closure
 - Part 1 – Shutdown Activities
 - Part 2 – Preliminary Dismantling
 - Part 3 – Refurbishment
- Phase B – Care and Maintenance
- Phase C – Decommissioning
- Phase D – Green Field

HIFAR *transition* to Green Field





Where are we at?

- **November 2007** – Shutdown activities nearing successful completion
- **Planning** for dismantling and refurbishment underway – focus on QMS revision, safety analysis, characterisation, **dismantling**, design of refurbished systems and waste handling


HIFAR *transition* to Green Field





Phase A – Parts 2 & 3 Activities

- Master schedule incorporates multiple plans – QMS revision, Characterisation plans, dismantling plans etc..



HIFAR *transition* to Green Field





Dismantling and Refurbishment

- 24 Major Dismantling Projects
- 10 Major Refurbishment Projects

HIFAR *transition* to Green Field





Typical Dismantling/Refurbishment Project

- Projects follows existing Project Management protocol involving hold points to allow independent safety and regulatory assessment
- Project engineer defines resource and expenditure requirements
- Cost, durations & deadlines stipulated
- Project plan is incorporated into master schedule – any inter-dependencies are resolved

HIFAR *transition* to Green Field





Typical Dismantling/Refurbishment Project

- Quality plan
- Task specification
- Project plan & schedule
- Conceptual design, cost estimate & review
- Detailed design and drawings
- **Safety analysis and submission**
- Engage contractors
- Purchasing and installation
- Testing & Commissioning
- **Waste Management Report**
- Update manuals, drawings, procedures, training
- **Completion submission and checklist**

HIFAR *transition* to Green Field





Dependencies

- Majority of dismantling projects are somewhat independent from other projects outside of accessibility issues
- Otherwise:
 - Availability of waste route (major waste processing facility unavailable until 2009)
 - Refurbished electrical systems reliant on new power supply

HIFAR *transition* to Green Field





Major Milestones for Phase A

- Completion of Phase A, Part 1 (May 2008)
- Clear out Cooling Tower site (November 2008)
- New electrical power supply system (April 2009)
- New HVAC system (August 2009)
- Completion of Phase A (January 2010)

HIFAR *transition* to Green Field





Major Milestones for Phase A

- Electrical refurbishment projects (new power supply and HVAC) are on critical path for the majority of Phase A

HIFAR *transition* to Green Field





Why Perform Characterisation Work?

- Determine the amount of radioactive waste to be generated
- Do you have a place to put it?
- Can you handle it? What doses are expected?
- Help assess risk, assess costs
- Determine site remediation work

HIFAR *transition* to Green Field





Project-based Characterisation

- Project-based characterisation for preliminary dismantling
- Based on known history, potential transport of radioactive material, neutron activation fields and maintenance of systems, **waste routes are available** for the majority of systems planned for dismantling
- **Large contaminated** items **will have to wait** until 2009 when a new waste facility is commissioned

HIFAR transition to Green Field





Dismantling

- Tritium contamination is a low energy beta emitter and is easily shielded
- Simple dosimeter measurements may not suffice

HIFAR *transition* to Green Field





Cooling Towers Site Remediation

- Biased sampling of pond concrete, surroundings and pipework based on known events and operation
- Check for migration of hazmat to underlying strata
- Conformance to state-based environmental legislation



HIFAR *transition* to Green Field





Cooling Towers Site Remediation

- Groundwater and air sampling carried out on a regular basis
- Groundwater at site is ~35 Bq/L (Nov 05) (Aus Drinking Water Guideline is 7600 Bq/L)
- Review of monitoring history

HIFAR *transition* to Green Field





Radiological Characterisation Plan for HIFAR

- Cumulative flux at site of activation (by in-situ measurements and analytical methods)
- **Calculate** and then **verify** calculations with radiological surveys and information from similar reactors

HIFAR *transition* to Green Field





Radiological Characterisation Plan for HIFAR

- Review of historical information to determine megawatt days, abnormal occurrences
- Estimates made by scaling results obtained from Danish DIDO class reactor DR-3 characterisation
- Sampling plan to be prepared after a review of sampling plans conducted for other DIDO class reactors
- Majority of activity due to ^{60}Co
- Follow principles from MARSSIM
- Develop site remediation plan



HIFAR *transition* to Green Field





Scaling of DR-3 Analysis

Estimated HIFAR T2 Borehole activity in October 2009





HIFAR *transition* to Green Field





Scaling of DR-3 Analysis

HIFAR V2 Borehole activity in August 2011




HIFAR *transition* to Green Field





Radiological Analysis

- Monte-Carlo analysis of 3D model of HIFAR to determine flux
- Subsequent analysis to determine activation and decay



HIFAR *transition* to Green Field





Long-term characterisation – Waste Estimates

- Final decommissioning dependent on National Waste Repository
- 2005 waste estimates for decommissioning of HIFAR:

Type of waste	Amount of material (t)	
	Transition Work	Decommissioning
Inactive	196	5,300
LLW	130	460
Long-lived ILW	1.9	499

HIFAR *transition* to Green Field





Are all the Nasties Covered?

- Don't forget non-radiological characterisation for decommissioning and remediation: hazardous materials such as asbestos, PCBs, lead, heavy metals, other chemicals etc..

HIFAR *transition* to Green Field





HIFAR **Q**uality **M**anagement **S**ystem (**QMS**)

- Safety Procedures
- Operating Instructions
- Definition of staff hierarchy and authorities
- Maintenance Instructions
- Project Management Protocol

HIFAR *transition* to Green Field





Why use a QMS?

- Ordered system by which staff can work by
- If something goes wrong, recording systems may track down cause of the problem
- Consistency
- Serves as a knowledge bank
- Enforces a culture of safety and responsibility

HIFAR *transition* to Green Field





Revision of QMS for Transition

- Revised QMS developed after study and consensus is reached with relevant parties
- New **staff structure** is defined
- Authorities are defined internal and external to the immediate group including **maintenance, safety, waste handling**
- New **limits and conditions** are defined (rad & tritium monitors, health physics surveillance, rad stack discharge, building DAC, admin of hazmat)

HIFAR transition to Green Field





Revision of QMS for Transition

- Revised QMS is simpler to reflect the simpler nature of the plant → about 180 out of over 800 procedures kept
- QMS revision can be a large undertaking and requires some level of rationalisation

HIFAR *transition* to Green Field





Australian Government

Ansto

QMS for Transition

Good QMS = Good Management



HIFAR *transition* to Green Field





Summary

- 3 years in transitional work after shutdown
- Characterisation work: project-based for transitional work and major plan to determine final decommissioning and remediation
- QMS revision: an important management task

HIFAR *transition* to Green Field

