Characterization Plan

Reactor Bay Reactor Grounds East Wing

PNRI

7 December 2007

Components of the plans

- Survey requirements
- Methods chosen
 - Data gathering methods
 - Quality assurance
 - Waste management program
 - Safety program
 - Emergency program
 - Preparation of survey report
- Personnel & equipment
- Work schedule

Survey requirements

- Produce reliable and sufficient data to support decommissioning plan
- Radiological & non-radiological safety

- Information gathering
 - Drawings and photos
 - Operational history and records
 - inventory of radionuclides
 - previous monitoring data
 - incident reports
 - Personal recollections

- Survey preparations
 - Preliminary categorization of areas
 - Control room / sample room / instruments room
 - Pre-survey inspections
 - Clearing and cleaning
 - removal of fuel in the reactor bay
 - design of container
 - storage area
 - planning of transport
 - removal of other sources present
 - removal of other non-radioactive material
 - Making reference drawings
 - Establishing grid system

- Measurements
 - Reference background measurements
 - Field surveys
 - surface contamination scanning
 - air sampling
 - dose rate monitoring
 - in situ gamma spec
 - Sampling
 - concrete (core) sampling
 - soil sampling
 - paint sampling (for radiological & non-radiological)
 - swipe sampling
 - Metal/wood samples
 - water sampling
 - sludge/septic tank sampling
 - resin sampling
 - samples in pipes, ducts
 - sample preparations
 - Laboratory analysis
 - gamma spectroscopy
 - liquid scintillation
 - gross gamma/beta counting
 - alpha counting
 - xrf for non-radiological analysis
 - Ergonomics?

- Data analysis / decision making
 - Category reclassification if required
 - Comparison to clearance levels

Quality Assurance

- Identification of measurements
- Equipment calibration
- Validated procedures
- Personnel qualifications/training
- Record keeping
- Security
 - Area
 - Source
 - Data

Waste Management Program

- Radioactive wastes
- Non-radioactive wastes
- Storage / disposal area

Safety program

Radiation protection

- Dose constraints
- Protective clothing
- Personnel monitoring
- Shielding
- Contamination controls

Non-radiological safety

- Industrial safety
- Ventilation system
- → Health

Emergency program

- First aid
- Incidents (fire, earthquake, power interruptions, etc.)
- Accidents

Preparation of survey report

- Radionuclide/radioactivity maps
- Databases

Personnel

- Number of personnel
- Level of expertise and training requirements
- Team responsibilities (team leader, surveyor, health physicist, map maker..)
- 2 teams of 5 for field survey
- 2 teams of 3 for sampling
- 1 team, 6 members for laboratory
- 1 team, 6 members for clearing and cleaning
- 2 for data management

Instrumentation & equipment

- Survey meter (3)
- Contamination meters (3 for alpha, 3 beta/gamma)
- Teletectors (2)
- Portable gamma spec (2)
- Air sampler
- Diamond core drill
- Reference sources
- HPGe Well detector
- LSC
- XRF
- Gross Gamma/beta/alpha counters
- Alpha spectrometers
- Assorted common tools

Work schedule

						Month 1	Month 2	Month 3	Month 4	Month 5	Month 6	Month 7	Month 8	Month 9
	Data gathering (essentia		(essentially	y completed	d)									
	Survey preparations													
		insturment setup			<									
		pre-survey												
		clearing and cleaning												
		making of reference drawings and grid system												
Н														
	Measurements													
		field surveys												
		sampling												
		sampling preparations												
		laboratory analysis				<								
	Preparation of survey report													
	Ţ,		-											