

Decommissioning of Hot Cells at the Karlsruhe Reprocessing Plant (WAK)



Dr. W. Dander

Head of Department Dismantling and Decommissioning



Dipl. Ing. W. Lutz

Foreman Dismantling and Decommissioning WAK Process Building

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK



MA



Decommissioning Steps



Decommissioning of Hot Cells at WAK

Remote Dismantling		
 local dose rate: 	>	0.5 mSv/h
 object surface dose rate: 	>	100.0 mSv/h
 conventional human safety risk: 		high
Semi-remote Dismantling		
 local dose rate: 	~	0.5 mSv/h
 object surface dose rate: 	<	100.0 mSv/h
 conventional human safety risk: 		low
 Manual Dismantling 		
 local dose rate: 	<	0.5 mSv/h
 object surface dose rate: 	<	2.0 mSv/h
 conventional human safety risk: 		low

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK

WAK 5



10.07.2009/LR/W.Lutz

Remote Dismantling





Semi-remote dismantling in the pipe duct using a hydraulic shear on a crane hook. The shear is operated from a shielded working platform.

WAK-

Radioactive Contamination: Individual Protection on Site

Surface contamination		Safety measures
α-activity (Bq/cm ²)	β-activity (Bq/cm ²)	
≤ 0.05	≤ 0,5	Hot-zone protective clothing
> 0.05 ≤ 0.5	> 0.5 ≤ 5	Additional: • glove • overshoe • mask
> 0.5 ≤ 5	> 5 ≤ 50	Additional: • glove • overshoe • mask • fleece overall
> 5 ≤ 50	> 50 ≤ 500	Additional: • non-ventilated protective suit • mask
> 50	> 500	Additional: ventilated protective suit mask

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK



fleece overall

Decommissioning of Hot Cells at WAK





Direct measurement for room air monitoring BA33



Sampler for room air monitoring

Analysis of filters for room air monitoring



10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK







Cutting of fuel element racks by means of band saws



Cutting of pipelines by means of hydraulic shear



Dismantling in the valve gallery





Dismantling of the Pu evaporator box in cell VIII using a compass saw

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK



10.07.2009/LR/W.Lutz



Mechanical dismantling cell: Prior to and after removal of the stainless steel liner

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK



Mortising of concrete screed below the floor liner

WAK 17

WA





Upon completion of the disassembly work in room 259, the PVC floor cover was removed first. Then, all room surfaces and the surfaces of the walls, ceiling, and floor screed were ground of manually.

WAK 19

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK

Hot Spots in Room 259







Measurements revealed sharply confined hot spots on the floor, with the values measured reaching up to > 100,000 ips.

10.07.2009/LR/W.Lutz







10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK







Manual grinding





Manual grinding performance: About 2 m²/d

Layer thickness 2-3 mm





10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK





Double shaver head for mechanical surface removal

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK

WAK-



Forklift with attached shaver

10.07.2009/LR/W.Lutz

Decommissioning of Hot Cells at WAK



Shaver fixed to a modular rack

10.07.2009/LR/W.Lutz

WAK 32

WAK 31

Mechanical Surface Removal Data

Removal width	2 x 0.185 m = 0.37 m	
Removal rate	1.4 – 1.8 m/min	
Removal depth	3 mm	
Roughness depth	< 1 mm	
Rotating speed of shaver	1,800 rpm	
Theoretical removal rate	40 m²/h	
Range of shaver on a forklift (without change of position)	5 m height, 2 m width	
Range of shaver on a rack (without change of position)	9.7 m height, 2.6 m width	
Removed surface area (without change of position)	Shaver on forklift 10 m ²	
	Shaver on rack 25 m ² wall	
	5.5 m ² ceiling	
Daily performance, including fitting times	15 m²/d	
10.07.2009/LR/W.Lutz Decommissioning of Hot Cells at WAK 33		

Measurements in Room 259



A COMO instrument was used for the radiological measurement of the room surfaces

Decommissioning of Hot Cells at WAK

Sampling





In-situ Measurement Setup



