

WAK

**Wiederaufarbeitungsanlage Karlsruhe
Rückbau- und Entsorgungs- GmbH**

**Decommissioning Projects
at the
Nuclear Research Center Karlsruhe**

Wolfgang Pfeifer
Executive Director

***IAEA Workshop “Decommissioning Technologies”
July 06 - 10, 2009***

Contents of the presentation

- Situation in Germany concerning decommissioning of nuclear facilities**
- Overview of the activities of the company EWN and the status of decommissioning of nuclear facilities on the premises of the Karlsruhe research center**
- Recommendations of lessons learned**

Research Reactors in Germany with Thermal Outputs of 0.1 MW and more

Research reactor	MW _{th}	Operation	Status
FRMZ Mainz (TRIGA)	0.1	1965-	in operation
FRG-1, GKSS Geesthacht Research Center	5	1958-	decommissioned
BER-2, Hahn-Meitner Institute Berlin	19	1963-	in operation
FRJ-2, Jülich Research Center	23	1962-	decommissioned
FRM-II, University of Munich	20	2003-	in operation
HD TRIGA II Heidelberg	0.25	1978-	dismantled
FRM, University of Munich	4	1957-	decommissioned
FRH TRIGA, Medical University Hanover	0.25	1973-96	
FMRB, PTB Braunschweig	1	1967-95	decommissioned
FRN, GSF Neuherberg/Munich	1	1972-82	decommissioned
FRF-2, University of Frankfurt	1	1977-83	decommissioned
RFR, VKTA Rossendorf	10	1957-91	under dismantling
FRJ-1, Jülich Research Center	10	1962-85	under dismantling
FRG-2, GKSS Geesthacht Research Center	15	1963-95	decommissioned
NS Otto Hahn (nuclear ship)	38	1968-79	dismantled
FR 2, Karlsruhe Research Center	44	1961-81	in safe enclosure

Nuclear Power Plants and prototype reactors in Germany, which are currently being decommissioned

NPP unit	MW _e	Operation	Plant type
MZFR, Karlsruhe Research Center	58	1965-84	Heavy water-moderated PWR
KKR, Rheinsberg	70	1966-90	Pressurized water reactor of Soviet design
KGR-1, Greifswald	440	1973-90	
KGR-2, Greifswald	440	1974-90	
KGR-3, Greifswald	440	1977-90	
KGR-4, Greifswald	440	1979-90	
KGR-5, Greifswald	440	1989-90	
KMK, Mühlheim-Kärlich	1219		PWR, did not take up operation due to court order
VAK, Kahl	16	1960-85	Boiling water reactor
KRB-A, Gundremmingen	250	1966-77	
KWL, Lingen	254	1968-77	
HDR, Karlstein/Kahl, green field	25	1969-71	
KWO, Obrigheim	340	1968-2005	Pressurized water reactor (PWR)
KKS, Stade	640	1972-2005	PWR
KWW, Würgassen	670	1971-95	Boiling water reactor
KKN, Niederaichbach, green field	106	1972-74	Gas-cooled, heavy water-moderated reactor
AVR, Jülich	15	1966-88	Gas-cooled high-temperature reactor
THTR 300, Hamm-Uentrop	308	1984-88	Gas-cooled high-temperature reactor
KNK-II, Karlsruhe Research Center	20	1977-91	Sodium-cooled reactor
SNR 300, Kalkar	300	No operation	Completely dismantled

Fuel Element Fabrication Facilities and Reprocessing (without facilities in large-scale institutions)

Location	Fabrication	Operator	Status
Reprocessing facilities (WAK)	Uranium, PU	WAK/FZK	Operation 1972-91 under dismantling
NUKEM-old, Hanau		Nukem	Operation 1962-88 dismantling completed
NUKEM 2, Hanau		Nukem	Did not take up operation
HOBEG, Hanau	Fuel spheres for HTR	Hobeg	Operation 1972-88 dismantling completed
Uranium processing facility, Hanau		Siemens	Operation 1969-94 dismantling completed
MOX facility (old), Hanau	Mixed-oxide fuel elements	Siemens	Operation 1969-91 dismantling completed
MOX facility (new), Hanau		Siemens	Given up during construction (95% completed)
Fuel element fabrication facility, Karlstein		Siemens	Operation 1982-96, decommissioned, under dismantling
ANF Lingen		ANF	Operation since 1979
URANIUM Mines WISMUT	Uranium	WISMUT	Shut down 1991 remediation of the sites, nearly completed

Situation today

Decisions in 1989/90

- fast breeder reactor SNR-300 in Kalkar was not commissioned
- not to construct the industrial reprocessing plant at Wackersdorf

Major amendments of Atomic Energy Act 2002

- Use of nuclear energy is limited (17 NPP in operation today)
 - agreement between utility-companies and government
 - the last NPP will be shut down in 2020
- No new nuclear power station will be constructed
- Reprocessing of nuclear fuel is prohibited after year 2005

The EWN-Group



3000 km Murmansk

Task of EWN
decommissioning and waste management of nearly all nuclear facilities belonging to the public

Nuclear Sites and Subsidiaries

The EWN-Group



**EWN / ZLN GmbH
Greifswald**



Interim Storage North (ZLN)



Reactor Dismantling




The EWN-Group



Murmansk

3000 km



Submarine-Project

The EWN-Group



Transport of the Reactor Vessel

The EWN-Group



AVR GmbH
Jülich




Dismantling of the High-Temperature Reactor


Situation of the Karlsruhe Research Center




Research fields at FZ Karlsruhe




Nuclear Facilities Decommissioning Division at a Glance



Aerial View from the North to the Reactor Decommissioning Projects



Multipurpose Reactor (MZFR)



**1961 – 1965
Construction**




**1965 – 1984
Operation**



**1984 – 2012
Dismantling**


Compact Sodium Cooled Nuclear Reactor Facility (KNK)



1966 – 1969 Construction



1971 – 1991 Operation



**1991 – 2013
Decommissioning**

Future Project: Decommissioning of the Hot Cells (HZ)



2009 – 2012
Dismantling of the first sections

FR 2 Research Reactor

**D2O-moderated research reactor
44 MWth (neutron source)
Operation 1961-1981**



**Dismantling of experimental loops primary
and secondary system**


**Safe enclosure of the reactor block
1991 – 1996**

Decision today

complete dismantling

- **easy tools for remote dismantling available**
- **overall costs with dismantling after 30 year much higher**

Nuclear Facilities Decommissioning Division at a Glance



Fuel Reprocessing Plant WAK



Reprocessing Building

Reprocessing Building

- 2000 t of process equipment dismantled out of it 100 t remote controlled
- 1200 t of debris disposed
- 98% of the radioactive inventory (4,8E14 Bq) disposed of as low active waste (interim storage)


Fuel Reprocessing Plant WAK



Reprocessing Building

- 2000 t of process equipment dismantled, out of it 100 t remote controlled
- 1200 t of debris disposed
- 98% of the radioactive inventory (4,8E14 Bq) disposed of as low active waste (interim storage)


Fuel Reprocessing Plant WAK



Reprocessing Building

- 2000 t of process equipment dismantled, out of it 100 t remote controlled
- 1200 t of debris disposed
- 98% of the radioactive inventory (4,8E14 Bq) disposed of as low active waste (interim storage)


Fuel Reprocessing Plant WAK



HLLW-Storage Facilities

- 60 m³ HLLW, 7,7E17 Bq, 500 kg Uran, 16,5 kg Plutonium
- LAVA in operation
- HWL out of operation (spare storage after maintenance)
- HLLW facilities technically separated


Fuel Reprocessing Plant WAK




Liquid fed ceramic melter

- HLLW feeding rate 10 dm³/h
- Glass production rate 6,7 kg/h
- Joule heating 35 kW
- Glass tank capacity 400 kg

Waste Treatment and Storage at the EWN Group



Waste Management Facilities (HDB)



Compaction



Decontamination




Disassembling



ILW Handling

Radioactive Waste Processing Paths



Waste Management Facilities (HDB)



Product Control



Product Control



Interim Storage

Contents of the presentation

- Situation in Germany concerning decommissioning of nuclear facilities
- Overview of the activities of the company EWN and the status of decommissioning of nuclear facilities on the premises of the Karlsruhe research center
- Recommendations of lessons learned

Preparing D&D Work

First Step:

- Complete recording of the nuclide inventory (nuclide composition / level of contamination)
- Documentation of construction and building (e.g. installation)

Second step:

- Upgrade of safety barriers (no spread of contamination outside and to the staff)
- Upgrade of ventilation systems including control systems of released radioactivity
- Upgrade of cranes

D&D Strategies

- ❑ **Complete decommissioning including waste management**
- ❑ **Partitioning of the whole decommissioning project in different parts (manageable duration), each with own license**
- ❑ **Basic rules for D&D:**
 - **as simple as possible**
 - **if possible, using standard tools for dismantling**

Waste Management

- If possible, waste management on site

- Necessary waste management facilities:
 - Treatment of liquids (evaporation, cementation)
 - Possibilities for decontamination and release of materials
 - Cementation of concentrates and solid waste
 - Super compaction
 - When indicated, facility for drying (increases long time stability of the waste)
 - Existence of adequate and proofed mobile facilities

Basic Conditions for Waste management

- Possibilities for clearance
(to be established by authorities)
- Safe interim storage
(even for longer periods of time)
- Final disposal

Waste Management

Immediate packing of the waste using

– Drums



– MOSAIK containers



– Containers (stackable and stable)



Summary

- ❑ **Germany has a lot of D&D experiences**
- ❑ **Experience of the Karlsruhe Decommissioning projects and of waste management can be used for smaller nuclear facilities and laboratories**

I wish you a pleasant week with a lot of impressions and information which are useful for your own decommissioning projects