

Procedure for Site Release

Group 2

Ms. C. S. Virtopeanu, Mr.G.Nabakhtiani

*Mr.C. Litescu, Ms.T.Kilochytska, Mr.G.Tavcar,, Mr.O.Slavik, Mr.
R.Krujalkas, Mr. J.Malnacs, Mr. A.Abramenkovs, Ms. B.A. Ahmed,
Mr.J. Mudra, Mr. P.H. Pham, Mr.R. Anasco, Mr.G.Kiknadze,*

Site Release strategy


- National legislative requirements (release criteria)
- International Recommendations (IAEA, EU and others)
- Definition of end point for the site (Green or Brown field)-Assessment criteria:
 - Site composition,
 - Protection of underground water
 - Cost benefit analyzes




Site Characterization

- General conditions of whole site (pond inside the nuclear installation);
- The history of use of the site;
- Location of the facility and its present situation,
- Description of waste water and other waste stream:
 - ✓ Research reactor
 - ✓ Radiochemical laboratories
 - ✓ Reprocessing of irradiated fuel elements











Survey Strategy

- Assessment of the scope of the survey (by core drilling)
- Definition of measurement technique according to existing nuclide distribution and condition of the structures, depth of concrete.
- ✓ Taking the samples; for radiochemical analyze,
- ✓ In situ measurement;
- ✓ surface contamination measurement Nuclide vector for different materials and places (as were defined before)
- Report to RB



Equipment

- HpGe spectrometer
- Portable radiometers (Contamat FHT-111M, Radiogem 2000 and others)
- Portable and stationary Scintillation spectrometers and detectors (Inspector 1000, Field spec, Eberline FH-40GX and others with teleprobe)
- Alpha spectrometer
- Multichannel analyzer
- Liquid scintillation counter

Survey

Develop initial survey plan to be approved by RB:

- Concrete structure survey, 1x1 m², average Soil Survey (around and below the structure) – drilling on bottom, about 20 core samples
- Survey of all other auxiliary systems (pipes, shafts, paved areas other structures)
- Assessment of visual damages on the structure (possible additional core samples)
- Assessment of ground water for possible contamination and its spreading
- Conduct the survey
- Compliance with release criteria



Decontamination



- Assessment of survey results
- Elaboration of Clean up Plan to be approved by RB (if it is needed)
- Definition of decontamination tools:
 - ✓ Working areas establishment,
 - ✓ Dry cleaning;
 - ✓ Management of the secondary waste (treatment of concrete and others),
 - ✓ Management of contaminated soil,
 - ✓ Material clearance assessment
- Decontamination on elevated places of the facility
- Decontamination control


Cost

- Release alternatives
- Site remediation
- Measurement equipment,
- Decontamination equipment,
- Dismantling equipment,
- Labour cost
- Management of radioactive waste
- Logistic
- Auxiliary systems
- Expertise
- Other cost
- Regulatory approval



Radiation Protection

- Establishment of radiation protection programme approved by RB:
 - ✓ ALARA principle,
 - ✓ Working rules;
 - ✓ Workplace monitoring,
 - ✓ Individual dose monitoring,
 - ✓ Definition of PPE
 - ✓ Arrangement of decontamination for workers
 - ✓ Definition of zones
 - ✓ Security control
 - ✓ Development QA programme and QC procedure
 - ✓ Development of Emergency response plan
- Environment monitoring
 - ✓ Dose assessment
 - ✓ Sampling and others



ALARA



End point

- Final report approved by RB:
- The conditions for restricted use:
 - ✓ To demolish or use (for example storage place or other)
- Definition of the restrictions
 - ✓ Time schedule,
 - ✓ Access control,
 - ✓ Environmental monitoring programme (if other nuclear installation does not exist)

