



**Siempelkamp**

NIS Ingenieurgesellschaft mbH

**VAK GmbH**

# **Unrestricted Release of Buildings and Site of NPP Versuchsaatomkraftwerk Kahl - VAK**

**Ingolf Auler, NIS  
Gerald Rudolph, NIS  
Walter Hackel, VAK**

**IAEA Training Course on Release of Sites and Building Structures, Karlsruhe, 27. 09. - 01. 10. 2010**

# Unrestricted release of VAK

## Contents of presentation

- **History and initial situation**
- **Procedure release of buildings**
- **Results of release of buildings**
- **Procedure release of site**
- **Results of release of site**
- **Lessons learned**
- **Consequences of lessons**

# Unrestricted release of VAK

## VAK History



- **First NPP in Germany**
- **Operator: Versuchsatomkraftwerk GmbH**
  - Shareholder: RWE 80% - E.ON 20%
- **Type: dual circuit BWR 16 MW electrical**
- **Supplier: AEG, Germany / GE, USA**
- **Erection: 1958 – 1960**
- **Operation: 1960 – 1985**
  - Fuel Testing programs, operational experience, personnel training
- **Production: 2,1 TWh**
- **Start decommissioning: 1988**
  - 1988 – 2001: by VAK GmbH
  - 2001 – 2008: by NUKEM Technologies GmbH
  - 2008 – 2010: by VAK GmbH / NIS
- **Green field: October 2010**

# Unrestricted release of VAK

## Initial situation I

### VAK specific rules and standards for release

- **4. Decommissioning licence of 12.01.2000 (4. StG)**
  - 4 Nuclide vectors
  - Their examination during application
- **Operations Manual (BHB) with Radiation Protection Rules (SSO)**
  - Procedures for different types of material
  - Specification of averaged surface and mass for clearance measurements
  - Reference of clearance values to § 29 Radiation Protection Ordinance (StrlSchV)
  - Procedures for possible changes
- **Organisation Manual (OHB) with Operational Instructions**
  - Reference to operational history
  - Reference to specific buildings and site areas
  - Specification of measuring methods, size of sampling
  - Examination of nuclide vectors
- **Working procedures and worker briefing**
  - Procedures for decontamination, requirements for release, industrial safety

# Unrestricted release of VAK

## Initial situation II

### Advancing state of the art

- **Amended German Radiation Protection Ordinance (StrISchV) in 2001**
  - Release limits more specific; partly much lower (column 7 – site areas)
  
- **Enhanced German Standard DIN 25457, parts 6 and 7**
  - Detailed, conservative specifications of release procedures,
  - Statistic procedures for locations of measuring and sampling
  
- **Enhanced generale licensing**
  - More restrictive
  - More focused to decommissioning

# Unrestricted release of VAK

## General performance

### Steps of performance

- Radiological characterisation
- Decontamination, attendant measurements and conditioning of materials
- Clearance measurements by licensee<sup>1</sup>
- Control measurements / approval of release by authority
- Disposal of released materials and radioactive waste
- Release from application of German Atomic Act (AtG)

# Unrestricted release of VAK

## Release of buildings



Contamat Measurement



Core drilling



Marking of contaminated areas

## Radiological characterisation

Identification of nuclide vectors and distribution of radioactivity

- Scanning of surfaces
  - Large area gas flow counters (Contamat)
  - Gamma scintillation counters (Scintomat)
- Evaluate depth profile on selected locations
  - „Stocker“-sampling, stepwise 2-5 cm
  - Core drilling
  - Analysis of samples at the Radlab
- Smear tests
  - Remaining equipment, e.g. fastening bars anchor slabs
- Marking the relevant areas on the spot
- Documentation of initial radiologic. situation

# Unrestricted release of VAK

## Release of buildings



Marking hotspot



Removal by scabbling

## Surface decontamination

- **Removal of local, near to surface „Hot Spots“ (< 2 cm) e.g.:**
  - Material failures and crevices
  - Fastening bars
  - Wall plugs
  
- **Removal of large portions of surface by:**
  - Shaving
  - Steel shot blasting
  - Scabbling
  - Milling, wall / floor



# Unrestricted release of VAK

## Release of buildings



Removal by manual pneumatic hammer

## Surface decontamination

- **Migrated contamination or activation (> 2 cm)**
  - Deep material failures or crevices
  - Pipe penetrations,
  - Constructive gaps
  - Narrow rooms, wells
  
- **Deep removal**
  - Manual pneumatic hammer
  - Core drilling
  - Pneumatic rock excavator
  - Diamond wire saw (special cases only)

# Unrestricted release of VAK

## Release of buildings

### Reactor building: Radiological characterisation

#### ➤ Results

- Deep (->70 cm), partly extensive migration of radioactivity into internal building structures

#### ➤ Consequences

- Removal of hotspot areas (radwaste) before demolition of internal building structures to avoid dilution of radioactivity
  - Surface specific release: „Col. 10 – buildings for demolition“: e.g. Co60: 3 Bq/cm<sup>2</sup>
- Demolition of all internal structures inside steel containment before clearance measurements
- Change of general procedure according to 4. Decommissioning Licence

# Unrestricted release of VAK

## Release of Reactor Building structures



Removal by  
pneumatic rock excavator



Removal by diamond wire saw

**Decontamination of all contaminated or activated structures**

- **Complete removal of walls and floors**
- **Consideration of static requirements of remaining structures**
- **Elevation-wise demolition of Reactor Building internal structures**
  - **Pneumatic rock excavator**
  - **Diamond wire saw (special cases only)**

**Mass specific clearance measurements**

- **Mass specific release: „Col. 6 – building rubble“:  
e.g. Co60: 9E-2 Bq/g**

# Unrestricted release of VAK

## Release of buildings



Concrete breaker at controlled area

**Mass specific clearance measurements by licensee**  
(radioactivity migrated into building structures)

- **Conditioning of material to be measured**  
(Breaker, filling of drums)
- **In-situ-gamma spectrometry on drums**  
(alternatively: gross gamma measurements)



Filling of drums with concrete rubble



In-situ measurements of drums

# Unrestricted release of VAK

## Release of buildings




In-situ gamma spectrometry on steel containment

### Surface specific clearance measurements on structures by licencee

- In-situ gamma spectrometry, whole controlled area
- Alternatively measurements by Contamat on areas difficult to access
- Evaluation of depth profiles on selected locations by „Stocker“-sampling

The results of the final measurements were documented



In-situ gamma spectrometry



Measurements from lifting gear



Marking after in-situ measurements

# Unrestricted release of VAK

## Release of buildings

### Advantage of in-situ-gamma spectrometry

- **Measurements consider also migrated radioactivity and activation inside building structures**
- **Calibration adaptable to measuring problem e.g. in relation to surface, mass and depth**
- **Facilitates selective identification of gamma nuclides**
- **Limited identification of low energy gamma radiation (e.g. Am 241)**

# Unrestricted release of VAK

## Release of buildings



Control measurements by in-situ gamma spectrometry

### Control of measurements / release by authority

- Checking of „final state“ documentation
- Inspection of „initial state“ and documentation of „accompanying measurements“
- Control measurements (In-situ, Contamat und depth profile)
- Written confirmation of release

# Unrestricted release of VAK

## Results of release of buildings

### Reactor building

- **Duration in total 24 months;**  
thereof 12 months for removal of internal concrete structures

#### **Mass specific clearance measurements - internal concrete structures:**

- Mass of concrete 4.200 Mg -> filling into 200 I-drums
- Number of 200l-drums 14.000 -> in-situ drum measurements
- Control measurements by authority 2.100 drums (15%!)
- Cost of release procedure 2.300 €/Mg in total

**The internally demolished and on its inner surface already released reactor building (steel containment) were afterwards cut into pieces and the pieces were measured from outside too**



# Unrestricted release of VAK

## Results of release of buildings

### Waste treatment building (AG) and multi-purpose hall (MZH)

- **Duration** ca. 18 months
  
- **Internal surface** ca. 9.300 m<sup>2</sup>
- **Number of measurements**
  - In-situ (ca. 80 % of surface) ca. 2.900
  - Contamat (ca. 20 % of surface) ca. 118.000
  - Material and stocker samples ca. 1.400
  
- **Specific costs**
  - AG: pre-measurement, decontamination of surfaces, removal of some internal walls\* > 300 €/m<sup>2</sup>
  - MZH: pre-measurement, decontamination of surfaces and clearance measurements ca. 250 €/m<sup>2</sup>

\* without clearance measurements

# Unrestricted release of VAK

## Release of site

### Radiological characterisation: sampling program


- Verification of nuclide vectors
- Evaluation of depth profile in soil
- Examination of foreign contamination  
(Cs137, Sr90: bombs fallout, ChNPP 1986)

#### ➤ Internal VAK site

- Paved surfaces
- Unpaved surfaces
- Sampling on surface layer, drill core soundings

#### ➤ Outside VAK site

- Sampling on surface layer
- Literature study
- Experience from dismantling of the adjacent, already dismantled HDR plant



# Unrestricted release of VAK

## Release of site

Examination of foreign contamination (RCh): Sampling on surface layer  
**Foreign contamination partly in the range of release limits!**

NUKLIDE	Release limits StrISchV, Tab1, col. 7 mBq/g	Measured RCh VAK mBq/g	Measured outside+literature mBq/g	Deducted foreign contamination mBq/g
Co 60	30	< 0,5	---	---
Sr 90	2	< 5	2 - 9	2
Cs137	60	18 – 330	8- 590	10

# Unrestricted release of VAK

## Release of site



Drill core soundings on the site

## Drill core sounding (RKS)


Drilling pattern	1-2/400m <sup>2</sup>
Number of RKS	108 x 2 m deep 14 x 8 m deep
Additional	20 below buildings
Number of licensee samples	600
Max. measured value	Cs 137 < 9 mBq/g Co 60 < 6 mBq/g
Number of TÜV samples	147 (~25%!)



Sampling from drill core sounding

# Unrestricted release of VAK

## Release of site



**Collimated in-situ gamma spectrometry  
on paved areas of the site**

# Unrestricted release of VAK

## Release of site



**In-situ gamma spectrometry  
on unpaved areas of the site**

# Unrestricted release of VAK

## Results of release of site

- **Surface of site** **ca. 24.800 m<sup>2</sup>**
  - Paved surfaces ca. 15.800 m<sup>2</sup>
  - Unpaved surfaces ca. 9.000 m<sup>2</sup>
  - Former controlled area ca. 5.800 m<sup>2</sup> -> 100 % in-situ
  - Former supervised area ca. 19.000 m<sup>2</sup> -> 30 % in-situ
- **Number of in-situ measurements (4m<sup>2</sup>; 1m<sup>2</sup>)** **ca. 3.600**
  - Paved surfaces (up to 2 cm deep) ca. 1.200
  - Unpaved surfaces (up to 10 cm deep) ca. 1.400
  - Additional after decontamination ca. 1.000
- **Number of measurements by TÜV** ca. 500 (~ 14%!)
- **Efforts**
  - Measurements ca. 40-60 min each
  - Preparation / QA of measuring techniques ca. 60 min/day

# Unrestricted release of VAK

## Disposal of released material



Concrete breaker unit



Intermediate storage of cleared concrete rubble

## Disposal of released material

- Unrestricted disposal
- Reutilisation at landfill sites
- Disposal at municipal repositories
- Backfill at building pits  
(for VAK rejected by Authority)



# Unrestricted release of VAK

## Lessons learned

- **Operational documentation insufficient for decommissioning**
- **Contamination on RG-/AG-structures considerable deeper than expected**
- **Planned execution of RG´s demolition had to be changed**
- **Substantial more efforts to avoid dilution of activities during demolition**
- **Qualification of new measuring techniques**
- **Considerable more efforts for dismantling, decontamination and clearance under controlled area conditions**
- **Increased amount of radioactive waste due to deep migrated contamination**
- **External foreign contamination made the release of site more difficult**
- **Rise of requirements for the clearance procedures increases efforts**
- **Efforts of independent experts (TÜV) rose strongly**

# Unrestricted release of VAK

## Consequences of lessons

- **Documentation during plant operation should also targeted to later dismantling**
- **Radiological characterisation should start asap**
- **Planned procedures should be early discussed with authorities**
- **Different measuring techniques should be applied**
- **Qualification of measuring techniques should be discussed with authority/TÜV**
- **Licence should be open for changes to new techniques**
- **Linking of decontamination of surfaces with measurements should be considered**
- **Fair accounting modes between customer and contractor**

# Unrestricted release of VAK

## Dismantling after release of site



Demolishing waste treatment building



Demolishing turbine table



Crushing concrete structures



Lower part of reactor building



Filling reactor building pit below -4 m



Preparation of soil surface

# Unrestricted release of VAK

## Latest View to VAK site



Status of Green Field 23.09.2010

**Release of the former VAK buildings and site from application of German Atomic Act (AtG) will be officially declared on 22. October 2010 within a ceremony on site**



# Unrestricted release of VAK

## Nuclide Vectors\*

<b>Area</b>	<b>Co 60</b>	<b>Sr 90</b>	<b>Cs 137</b>	<b>Am 241</b>
RG	45 %	<1 %	54 %	< 1 %
AG	19 %	1 %	79 %	1 %
Site	8 %	2 %	89 %	1 %

\* Rounded values of reference nuclides 2009